

Annex-A

BoQ for Conversion of Old school to Girls Hostel

S #	Description	Quantity	Unit	Rate inclusive of taxes	Total Rs. inclusive of taxes
1	Cement Cherat/kohat/Eq	1500	Bags		
2	Sand	8000	Cft		
3	Crush	2000	Cft		
4	Bricks	120,000	Nos		
5	Steel Grade 40	26	Ton		
6	Binding wire	20	kg		
7	Steel ring	60	kg		
8	Supply & installation of Door frame 14 Gauge 39" x 7' (Steel)	24	nos		
9	Supply & Installation of Wooden Doors 39" x 7' with locks , bolts etc	20	Nos		
10	Supply & Installation of Bathroom doors frame 14-gauge, size 30" x 7' (Steel)	24	nos		
11	Supply & Installation of Wooden Bathroom doors, size 30" x 7', including locks, bolts etc	20	Nos		
12	Aluminium Windows 5' x 6'	24	Nos		
13	Bathroom ventilator Aluminium size 2' x 3'	24	Nos		
14	Supply & Installation of False ceiling sheets with aluminium frame 24" x 24" including formwork etc	6000	S.ft		
15	Floor tiles 16" x 16" Oriel / Eqv, Design & colour as approved by Director (Works)	600	Mtr		
16	Washroom wall tiles 18" x 36", Design & colour as approved by Director (Works)	280	Mtr		
17	Marble granite slab for vanity 40'X 2'	160	Sq.ft		
18	Tile bond	800	bags		
19	Tile Spacer	100	Packet		
20	Tile filling / grout	400	packet		
21	White cement	10	bags		

22	Glass wool insulation including installation complete in all respects	5600	Sq.ft		
23	Existing 02 nos of roofs rising to 3ft through Jack	02 nos	lumpsum		
24	Supply & Installation of Aluminium Main door 5'X8' with frame, lock, bolt etc	2	nos		
25	Emulsion off white Buxly	30	Bucket		
26	Emulsion white Buxly	20	Bucket		
27	Weather shield Buxly	15	Bucket		
	Sub Total (A)				
	PLUMBING WORKS				
1	English WC with seat cover Magma	20	Nos		
2	Vanity, Magma	20	Nos		
3	Bath set complete Faisal	20	Nos		
4	Accessories Set Faisal	20	Nos		
5	Looking Mirror 24" x 18"	20	Nos		
6	Waste cup tier-1	20	Nos		
7	Waste pipe tier-1	20	Nos		
8	CP Nipple 1", 1/2", 2", 3"	80	Nos		
9	Basin bolt tier-1	10	Nos		
10	PPR pipes 25 mm Kawsar/Equi	60	Lengths		
11	PPR elbow 25 mm	200	Nos		
12	PPR elbow 25 x ½	100	Nos		
13	PPR Socket 25 x ½	50	Nos		
14	PPR Tee 25 x ½	60	Nos		
15	PPR Socket 25 mm	60	Nos		
16	GI Nipple ½	30	Nos		
17	PPR Pipe 32 mm	40	Length		
18	PPR Elbow 32 mm	40	Nos		
19	PPR Socket 32 mm	30	Nos		
20	PPR elbow 32 x ¾	10	Nos		
21	PPR socket 32 x ¾	10	Nos		
22	GI Nipple ¾ HE	30	Nos		
23	PVC pipe 2" Kawsar/Equi	30	Nos		
24	PVC Pipe 3"	50	Nos		
25	PVC Pipe 4"	50	Nos		
26	Elbow PVC 2" 45 Degree	30	Nos		
27	Elbow PVC 2"	40	Nos		
28	elbow PVC 3" 45 Degree	30	Nos		
29	Elbow PVC 3"	40	Nos		
30	Elbow Pvc 4 " 45 Degree	20	Nos		

31	Plug Elbow 4" Pvc	20	Nos		
32	Elbow Pvc 4"	30	Nos		
33	Tee PVC 3"	20	Nos		
34	Tee PVC 4" x 3"	30	Nos		
35	P Tripp 4" Pvc	30	Nos		
36	P Tripp 3" PVC	60	Nos		
37	Multi P Tripp	20	Nos		
38	Solution PVC 500 Gram	20	Nos		
39	Thread	50	Nos		
40	Thread Tape	50	Nos		
41	Connection Pipe 24" Dawn	20	Nos		
42	Dead Plug 1/2" GI	60	Nos		
43	PPR Union 32 mm	10	Nos		
44	PPR Tee 25 x 32 mm	50	Nos		
45	PPR Socket 25 x 32 mm	30	Nos		
46	PPR Elbow 25 x 32 mm	20	Nos		
47	Floor waste/Drain Jalli	12	Nos		
	Sub Total (B)				
	Electrical items				
1	Exhaust Fans 10" Pak Fan	20	Nos		
2	Ceiling Fans 56" Pak Fan	50	Nos		
3	Heavy Sockets 3 Pin 15A with Pvc Box, Concealed OPAL /Eqv	50	Nos		
4	light Plugs Multi 5A with Pvc Box, Concealed OPAL/Equ	100	Nos		
5	LED Batten Light 2Feet 18W , Fast/Equ	100	Nos		
6	LED Batten light 4 Feet 36W, Fast /Equ	25	Nos		
7	5 Gang Switch with 3 On/Off Buttons and 2 , 2 pin sockets with Pvc Box, Concealed, OPAL/Equ"	30	Nos		
8	2 Fan Dimmers with On/Off Button with Pvc Box, Concealed OPAL/Equ	50	Nos		
9	4 Gang Switch with 3 Buttons & 1, 2 Pin Socket with Pvc Box, Concealed, OPAL/Equ"	20	Nos		
10	7 Gang Switch 5 buttons and 2 Sockets 2 pin with Pvc Box, Concealed, OPAL/Equ	10	Nos		
11	Pvc Pipe For Cables 1" Master,Popular/Equ	200	Lenths		
12	Pvc Pipes For Cables 0.75" Master,Popular/Equ	100	Lenths		
13	Pvc Pipe Sockets for 1" Master,Popular/Equ	200	Lenths		

14	Pvc Pipe Sockets for 0.75" Master,Popular/Equ	100	Lenth		
15	Pvc Junction Box Master,Popular/Equ	50	nos		
16	Cable 7/36 Red , Pakistan Cables	10	rolls		
17	Cable 7/36 Black, Pakistan Cables	10	rolls		
18	Cable 7/29 Red, Pakistan Cables	8	rolls		
19	Cable 7/29 Black, Pakistan Cables	8	rolls		
20	Cable 7/29 Green, Pakistan Cables	6	rolls		
21	Cable 3/29 Red, Pakistan Cables	10	rolls		
	Cable 3/29 Green, Pakistan Cables	8	rolls		
22	Cable 3/29 Black, Pakistan Cables	10	rolls		
23	Main Electric DB 3 Phase, with 10 Nos of 20A Breakers , 10 Nos of 10A Breakers, 1 Main Breaker 100A , Current & Voltage meters, Indicators and copper bus bars for load Distribution, Breakers Shneider with Import Documents/Verifiable through Schneider Application, DB size 14 Gauge GI , DB L & W Size as per requirement of mentioned Items.	2	nos		
	Sub Total (C)				
Grand Total (A+B+C)					

TERMS & CONDITIONS

1. Items will be supplied time to time as per demand of Works Department GIKI.
2. You are required to deliver the items at the specified time. However, after failing to do so, GIK reserves the right to forfeit an amount of 0.1% of the contract price per day and up to 10% of the cost of the project.
4. In case of any dispute, the decision of the Rector will be final and binding on you.
5. The rate must be quoted as per above format including all taxes, otherwise your quotation will be rejected / declared as nonresponsive.
6. **The firm must quote the price of all items, partial apply/bid is not accepted.**