

Annex-A

S. #.	Description Store Items.	Quantity Required	Unit	Rate (inclusive of taxes)	Amount (inclusive of taxes)
	REPAIR OF MAIN BOILER FOR HEATING SYSTEM MODEL NO. IME Eagle706/150/60				
1	Dismantling and removal of damaged/old boiler tubes	40	Nos		
2	Supply of boiler MS tubes 2"x12'(Natural gas) Huffaz seamless ASTM A192	40	Nos		
3	Replacement/fixing of new tubes complete with welding, expanding, Grinding and annealing works.	40	Nos		
4	Cleaning of internal shell of Boiler	01	No		
5	Cleaning of tube sheets (internal and external).	02	Nos.		
6	Repair work inside Boiler Shell - if required	01	No.		
7	Tuning and alignment of boiler burner	01	Job		
8	Hydraulic and operational testing of boiler	01	Job		
9	Replacement of furnace fire bricks and refractory if required.	01	Job		
10	Testing, Operating and commissioning of boiler complete in all respect	01	Job		
	TOTAL (Inclusive of Taxes)				

TERMS & CONDITIONS

1. Work will be required to be completed in 15 days from date of the issuance of Work Order.
2. Defect liability period shall be 30 days from the effective date of Taking over certificate.
3. You are required to complete the works within the specified time. However, after failing to do so, GIK reserves the right to forfeit an amount of 0.1% of the contract price per day and up to 10% of the cost of the project.
4. In case of any dispute, the decision of the Rector will be final and binding on you.
5. The rate must be quoted as per above format including all taxes, otherwise your quotation will be rejected / declared as nonresponsive.
6. **The firm must quote price of all items, partial apply / bid is not accepted.**