

Repair of Reciprocating Chillers Model: SKM WPCD 5272B

S. #.	Description Store Items.	Quantity Required	Unit	Rate inclusive of taxes	Amount inclusive of taxes
1	Dismantling of damaged / faulty compressors and shifting from chillers - 05 to serviceable chillers.	06	Nos		
2	Supply and gas charging of Refrigerant (R-22) Honeywell Genetron USA (Original)	10	Cylinders		
3	Oil charging in the repaired circuits - Suniso 3GS USA (Original)	10	Gallons		
4	Replacement of Drier core (Danfoss) as per existing specification	12	Nos		
5	Repair of Temperature controller in chiller No. 2 & 3	02	Nos		
6	Checking and repair of Complete control system of Chiller No. 4	01	Job		
7	Descaling of 3 condensers in each chiller	04 chillers (12 condensers)	Nos.		
8	Replacement of thermometers as per specification	24	Nos		
9	Replacement of pressure gauges as per specification	24	Nos		
10	Installation of compressors at serviceable chillers unit, leak testing, vacuuming and charging of Refrigerant upto required standard pressure. Testing, commissioning complete in all respect	01	Job		
Total Amount (Inclusive of Taxes)					

TERMS & CONDITIONS

1. Completion time of whole work is 30 days from the issuance of Work Order.
2. Defect liability period shall be 30 days from the effective date of Taking over certificate.
3. You are required to complete the work in the specified time. However, after failing to do so, GIK reserves the right to forfeit an amount of 0.1% of the contract price per day and up to 10% of the cost of the project. .
4. In case of any dispute, the decision of the Rector will be final and binding on you.
5. The rate must be quoted as per above format including all taxes, otherwise your quotation will be rejected / declared as nonresponsive.
6. **The firm must quote the price of all items, partial apply / bid is not accepted.**