

BILL OF QUANTITIES FOR
CONSTRUCTION OF 05 SECURITY PICQUETS

S. #.	Description Store Items.	Quantity Required	A/C Unit	Rate (Inclusive of taxes)	Amount (Inclusive of taxes)
	Supply, installation of following items including transportation, form work etc, complete in all aspects				
1	Steel ½ inches	2600	Kg		
2	Cement Kohat/equi	200	Bags		
3	Sand	800	Cft		
4	Crush	700	Cft		
5	Bending wire	3	Kg		
6	Steel stairs, 10' height (using 2" pipe)	05	nos		
7	Bricks	8000	Nos		
8	Excavation/form work/ labor charges	01	job		
9	Bracket fan Pak Fan	05	Nos		
10	12 watts LED light	05	Nos		
11	4 Gang switch	05	Nos		
12	Flood light 200 watts Fast Light	15	Nos		
13	16Ampere Breaker with Box Schnider	05	Nos		
14	Cable 7/29 Fast Cable black	08	Roll		
15	Cable 7/36 Fast Cable Red	08	Roll		
16	Cable 3/29 Fast Cable Green	08	Roll		
17	Pipe 3/4" popular	600	Mtr.		
	TOTAL (INCLUSIVE OF TAXES)				

TERMS & CONDITIONS

1. Contractors will have to make their own arrangement for all materials (except noted otherwise).
2. The contractor shall be responsible for the provision of electricity and water at site of work. The successful tenderer shall make his own arrangement for electric and water supply required for execution of work and of his work people or employees engaged thereon, whether or not a water supply/electric source exist on the site, and all expenses in respect thereof, shall be borne and paid by the contractor. In case the Water Supply and Electric connections are available, these will be charged according to GIK procedures. The contractor shall install his own energy/water at source to determine the amount of energy/water consumed.
3. Tender rates should be inclusive of all taxes and duties. Payable to Govt. and no claim on this account will be entertained.
4. It must be clearly understood by contractor that no claims on account of market fluctuations will be entertained during the currency of contract for any item of work included in the drawings attached to agreement in other words it may be clearly understood that no request for escalation of rates / Price adjustment will be entertained.
5. Client reserves the right to reject any or all tenders or to accept any tender without assigning any reason thereof and is not bound to accept the lowest tender.
6. Quoted rates shall remain valid for three months.
7. Damages for delay, in case of Non-completion of work within specified time would be @ 1% of tendered amount /day (10% max.)
8. No Mobilization advance will be paid.
9. Defect liability period, 02 x months from the completion date.
10. Participants shall inspect the site of work and surroundings and shall satisfy themselves before submitting their tenders as to the quantities and nature of works, climatic conditions, the locations, form and nature of the site and the terrain, the requirements and availability of manpower, labors, materials, water, electricity and roads, the means and access to the site,
11. Transportation and communication facilities and in general shall themselves obtain all necessary information as to cost, risks, contingencies, and other circumstances which may affect or influence their tenders. The costs of visiting the site shall be at the tenderer's own expense.
12. Time of completion of whole work is 30 days from the issuance of Work Order.
13. The work should conform to standard engineering practices on the subject and contractor will ensure the high quality thereof during execution. Utmost care/precautions must be observed while carrying out the work. Any damage done to the structures shall be at your cost & expense.

14. Payment shall be made on actual work done on site in instalments on basis of bill submitted. Payment will be released within 15 days of submission of verified contractor's bill from the engineer, after deduction of all applicable taxes.
15. In case of any dispute, the decision of the Rector will be final and binding on you.
16. Retention money @ 5% (Five Percent) of gross amount of Contractor's Running Bills shall be deducted and shall be released after completion of defect liability period.

