

Annex-A**CHANGE OVER SWITCH With Breakers**

S. #.	Description Store Items.	Quantity Required	Rate inclusive of taxes	Amount inclusive of taxes
1	Supply, installation, testing & commissioning of change over switch with below mentioned specs: a. Breaker main grid incoming 1000 Amp (Schneider / Eqv) b. Breaker generator incoming 400 Amp, (Schneider / Eqv) c. LT Cable 185 mm, 4 core, 15 meter (Fast/Eqv) d. Housing 14mm GI with IP65/66 rating including copper bus bars having current carrying capacity of 1000A with Current and Voltmeters. e. The breakers Condition should be new with import certification/proof of genuineness would be required.	One Job		

TERMS & CONDITIONS

1. Supply of whole items is 15 days from the issuance of Work Order.
2. Defect liability period shall be 90 days from the effective date of Taking over certificate.
3. You are required to deliver the items at the specified time. However, after failing to do so, GIK reserves the right to forfeit an amount of 0.1% of the contract price per day and up to 10% of the cost of the project.
4. In case of any dispute, the decision of the Rector will be final and binding on you.
5. The rate must be quoted as per the above format including all taxes, otherwise your quotation will be rejected / declared as nonresponsive.
6. **The firm must quote the price of all items, partial apply/bid is not accepted.**