Annex-A / BoQ

S. #.	Description Store Items.	Quantity Require d	Unit	Rate inclusive of taxes	Amount inclusive of taxes
1	Construction of Storeroom inside ZOO, size 14' x 12' Specifications: Civil works: Excavation in soft soil, foundation work 1:4:8 in foundation & brick work up to G.L, DPC 2" thick, brick masonry walls 9", 4 x R.C.C Column 9" x 9", Plinth beam 9" x 9" internal & external plaster work, PCC 1:2:4 Flooring, Pre cost roof slab, water proofing of roof, External & internal paint work, Steel Door 7' x 3.5', iron window 5' x 4' Etc. Complete in all respects. Electrical works: conduits & wiring, ceiling fan 56", lighting / 03 LED lights, fixing of light plug/power plug etc. All works according to engineering standards	01	Lumpsum		
2	Construction of Room with washroom in Nursery Room size: 14' x 12' Washroom Size: 5' x 7' Specifications: Civil works: Excavation in soft soil, foundation work 1:4:8 in foundation & brick work up to G.L, DPC 2" thick, brick masonry walls 9", 4 x R.C.C Column 9" x 9", Plinth beam 9" x 9" internal & external plaster work, PCC 1:2:4 Flooring, Pre cost roof slab, water proofing of roof , External & internal paint work, Steel Door having size 7' x 3.5', iron window having size 5' x 4' Etc. Complete in all respects. Electrical works: conduits & wiring, ceiling fan 56", Exhaust fan 12" lighting / 03 LED lights in room and one in washroom, fixing of light plug/power plug etc. Plumbing works: All type of plumbing / sanitary work including accessories required in washroom e.g providing & laying sewerage/sewage PVC 4", 3", 2" drain pipeline, PPR pipes & fittings, installation/fixing of Indian WC , wash hand basin, Bib cocks , tee cocks, looking mirror, wash basin mixer etc complete in all respect. All works according to engineering standards	01	Lumpsum		

TERMS & CONDITIONS

1. Time for undertaking whole Work is 30 days from the issuance of Work Order.

2. Defect liability period shall be 90 days from the effective date of Taking over certificate.

3. You are required to complete the work at the specified time. However, failure to do so, GIK reserves the right to forfeit an amount of 0.1% of the contract price per day and up to 10% of the cost of the project.

4. In case of any dispute, the decision of the Rector will be final and binding on you.

5. The rate must be quoted as per the above format including all taxes, otherwise your quotation will be rejected / declared as nonresponsive.

6. The firm must quote the price of all items, partial apply/bid is not accepted.

7. The work should conform to standard engineering practices on the subject and the contractor will ensure the high quality thereof during execution. Utmost care/precautions must be observed while carrying out the work. Any damage done to the structures shall be at your cost & expense.

8. Payment shall be made on actual work done on site in instalments on the basis of bill submitted. Payment will be released within 15 days of submission of verified contractor's bill from the engineer, after deduction of all applicable taxes.

8. Mobilization advance will not be paid.

9. You shall not assign or sublet the contract or its any part thereof any benefit or interest therein or there under without the prior written consent of the Client.

10. You shall make your own arrangement for electricity, water and storing belongings and the materials and for residence of staff / Labors.

11. The client shall have the right to discontinue or drop the work under this contract, whether in progress or otherwise, and to revoke the agreement without assigning any reason thereof by giving 7 days' notice. In that event, you shall have no claim for damages or compensation of any kind whatsoever. You shall, however, be entitled to receive the actual cost for the actual work provided and work completed by the contractor if found satisfactory.

2

Technical Evaluation Criteria

Credit Marks shall be awarded based on the following criteria. Minimumqualifying

	marks are 60.	
Sr. No.	Description	Maximum Points
i)	Projects of similar nature completed over last 05 years (5 marks each project)	35
ii)	Projects of similar nature in hand (5 marks each project)	35
iii)	Personnel / HR capabilities with CVs	12
iv)	Machinery & Equipment Capabilities	12
v)	Working Capital in last 3 years with reference to bank statement.	06
	Total:	100